

Surfacing- Asda Roundabout

SITE- Asda Roundabout, Tilbury

SIZE- 1,200m² of surfacing

SPECIALIST PRODUCTS USED- None

CLIENT- Graham

VALUE- £306,000.00



This job saw Henderson & Taylor completing a comprehensive resurfacing project on a busy 5-way roundabout, without closure. Access had to be maintained at all times to Asda and the port at Tilbury. As a result, works were completed on nights and at weekends to ensure that the roundabout did not have to close. The project required a considered Traffic Management plan which had to be deployed perfectly to allow consistent access.

The project consisted of new design levels, a profile plane and resuracing, establishing new crowns and kerb facing along the whole stretch. Works were completed over a weekend in April 2020 using one 8-man gang to complete the whole project.