Case Study Portfolio



Surfacing- Channels

SITE- Rectory Road, Chelmsford

CLIENT- Home Group

SIZE- 3,000m2 of surfacing

VALUE- £600,000.00

SPECIALIST PRODUCTS USED- Asphalt reinforcing membrane



The Channels project saw Henderson & Taylor creating an additional lane to ease traffic flow at the junction of Recotry Road with Chelmer Valley Road. The project involved planing out, embankment stabilisation, drainage, kerbing, utilities management, and surfacing, as well as building a tobermore retaining wall to widen the road without disturbing the adjacent cemetary.

Works were completed over 9 weeks, finishing 3 weeks ahead of programme. We operated mainly during normal working hours, with night closures scheduled for the surfacing shifts. Different gangs were used who specialised in their own aspects of the job.