

Road Construction- Colchester Road

SITE- Colchester Road, Chelmsford

SIZE- 7,000m²

SPECIALIST PRODUCTS USED- MMA High friction Surfacing

CLIENT- Home Group

VALUE- £2,000,000.00



Running from July 2018 to September 2019, the project saw the widening of existing Colchester Road to create an additional traffic lane and a combined cycleway/footway. This required widening construction, realignment of drainage, new street lighting, installation of a new signalised pedestrian crossing, numerous service diversions and protection works, full resurfacing of the carriageway, and all associated road marking and traffic signs.

Works were carried out by 2 4-man gangs, using a combination of day and night works to cause minimal disruption. Stakeholder collaboration was vital to ensure access for residents/local business. Narrow lane Traffic Management was used to ensure that access was maintained whilst preserving the welfare of the site team.