

Road Construction- Shell Haven Access Road

SITE- Shell Haven Refinery, Corringham

SIZE- 1,000m²

SPECIALIST PRODUCTS USED- None

CLIENT- Shell

VALUE- £850,000.00



Restabilising the access road into the Corringham Refinery involved excavating and removing flooded area soft spots before replacing them with rock-fill, overlaid with a reinforced concrete raft, with a final surface layer of asphalt, as well as all lining, signage, landscaping, and associated drainage works.

Working from January 2019 to May 2019, we used 2 5-man gangs to complete the project, using extended day shifts to minimise the length of the contract.

This reduced disruption of tanker movements in and out of the refinery.

Traffic Management was planned and managed to allow access at all times. We worked with the refinery shift pattern, and sequenced works with their fleet movements. This allowed Shell to operate as normal during the programme.