

## TBD - Barton Road, Cambridge

**SITE-** Barton Road, Cambridge

**CLIENT-** Milestone Infrastructure

**VALUE-** £350,000.00

**SPECIALIST PRODUCTS USED -** N/A



Henderson & Taylor were contracted by Milestone Infrastructure for works on improving this cycleway and junction at Barton Road, one of the busiest routes in Cambridge. The existing junction was overly complicated to navigate and did not give sufficient provision for active travel, and so a redesign was completed to include widening of the footway and carriageway, and new signals and crossings to improve safety and traffic flow.

The project included widening of the footway and carriageway up to binder course, ready for the red asphalt to delineate the cycle path from the footway, installation of channel kerbs to give distinction between the cycleway and vehicle traffic, improvement of the drainage system, installation of tactile crossing points for pedestrians, and installation of NAL sockets and connections ready for the traffic signals to be installed by the specialist contractor.

Works were completed between April and June 2023, over a 14 week period, working within the Network Management restrictions, with a team of 8.