

Footways Schemes - Wickhay, Basildon

SITE- Wickhay, Basildon

VALUE- £250,000.00

SPECIALIST PRODUCTS USED - N/A

CLIENT- Essex Highways

SIZE- 1570m² of carriageway and 400m² of footways



This project, on behalf of Essex Highways, required refurbishment of a carriageway and footway to improve access for residents of Wickhay, Basildon. The existing roadway was in disrepair and required updating.

Works commenced on the 28th of August 2023 and ran until the beginning of October. The carriageway was reconstructed and resurfaced up to 120mm depth, and footway was reconstructed with overlay up to 100mm depth. The scheme also required drainage repairs, kerbing, and associated civils works, including Jakoustic reflective fencing to reduce noise pollution to local households.

Works were completed during daytime hours under a road closure which could only be in affect for 8 hours per day. Access had to be maintained for residents at all times throughout the scheme, this was accomplished by good communication from the site team with local residents, who were all very pleased with the quality of works and attitude from the gang on the site.

Works were completed ahead of programme with great feedback from the client and residents. The newly refurbished access should provide safer, more accessible routes into the residents' homes.